

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 10W	C2
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/07/2010 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(C2) Quarter corner common to Sections 5 and 6. 1853 - Established by Geo. H. Cannon Deputy  
Surveyor, in a correctional survey, on the Section line between Section corners 40.72 chains south  
and 40.24 chains north. Old post. Beech 8 N15W 13 links, Beech 8 S15W 13 links. 1957 - Corner  
reestablished by proportionate measurement to the 1853 record by MI Dept. of Conservation personnel,  
who set wood post on the line between Section corners 40.42 chains south and 39.94 chains north.  
Aspen 6" S27W 31 links, H.Maple 6" N68E 38 links. 1974 - Billy D. Buckler RLS records that he  
reestablished the corner by proportionate measurement. Set 1" pipe with 4" alum. cap. 8" Maple S53E  
5.0', 8" Maple N14E 26.7'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(C2) Found the 1974 monument of record, in good condition, at record bearing and distance from the  
1974 witnesses, but did not accept it as marking the position for the corner. An examination of the  
field notes of the 1974 survey revealed that Mr. Buckler recovered the 1957 post and misinterpreted  
the 1957 field notes in a manner which caused him to believe that the 1957 post was in an erroneous  
position. In fact, the 1957 position was correctly established. Mr. Buckler measured 16.5' South  
and 16.5' East from the 1957 post, monumented that position, and removed the post. The 1974 monument  
not relied upon in the intervening years, I reestablished the corner position on the Section line  
between Section corners 2669.51' south and 2638.05' north, being proportionate to the 1853 record,  
and moved the 1974 monument to that position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(C2) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
12" Maple S40E 29.0' mrkd "1/4S NBT" 1974 NBT  
14" Maple N75E 23.9' do do  
10" W.Pine N57W 30.75' do  
10" twin Sugar S64W 29.45' do  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/26/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971