

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T R	
	T R	
	T R	
2. Property Controlling in Section	S 6 T 46N R 10W	14
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/07/2010 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(14-Sec. 6) South 1/16 corner between Sections 5 and 6. 1957 - Corner position established by MI Dept. of Conservation personnel midway and on the Section line between Section corner 20.36 chains south and 1/4 corner 20.36 chains north. Set wood post witnessed by H.Maple 5" S43E, 0.25 ch. 1974 Billy D. Buckler RLS records that he established corner between 1/4 cor. to north and Sec. cor. to south. Set 1" pipe with 4" alum. cap. 8" Maple S10W 36.0', 6" Maple S58E 5.5'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(14-Sec. 6) Found but did not accept the 1974 monument placed by Mr. Buckler. An examination of the field notes of the 1974 survey reveal that Mr. Buckler recovered the 1957 post and misinterpreted the 1957 field notes in a manner which caused him to believe that the 1957 post was in an erroneous position. In fact, the 1957 position was correct. Mr. Buckler measured 8.2' South and 8.2' East from the 1957 post, monumented that position, and removed the post. I reestablished the corner midway and on the Section line between Quarter and Section corners 1334.76' north and south and moved the 1974 monument to that position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(14) Set 1"IDx36" I.pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
10" Sugar S45E 18.25' mrkd "S1/16 BT"  
12" Sugar S01W 44.85' do  
12" R.Pine N47E 21.9' do  
10" W.Birch N25W 16.15' do  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/26/2010  
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971