

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>46N</u> R <u>10W</u>	<u>B5</u>
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 07/12/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B5) Quarter corner common to Sections 7-18. 1853 - Established by G.H.Cannon Deputy Surveyor during
a correctional survey of this township, S89 deg. 12' E 39.66 chains from Section corner A5 and West
40.31 chains from Section corner C5. Beech 10" S54 1/2 W 25.5 links, Y.Birch -- N5E 33.5 links.
1974 - Remonumented by Billy D. Buckler RLS: " Cor. set at wood post setting at SW corner of spruce
plantation. Re-established midway and on line bet. two section corners". NBT 4" W.Pine S5W 16.3'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B5) The original post and accessories were not recovered. Found the 1974 monument in good condition
and at record bearing and distance from the W.Pine NBT, now 12" DBH in good condition. Mr. Buckler's
statement that this corner was reestablished midway and on line between two section corners is not
correct, does not seem to apply to this corner, and its appearance in the record is taken to be the
result of a clerical error. The monument was recovered N89 deg. 57'19"E 2608.28' from Section corner
A5 and S89 deg. 47'44"W 2654.75' from Section corner C5 (true bearings), very near to the original
record distances, proportionate. I accept the monument as the best available evidence of the
position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B5) Found 1"ID I.pipe with 4" MDNR cap
Set measuring nail with MDNR tag in the side of:
12" W.Pine S10W 16.45' mrkd "1/4S" 1974 NBT
6" W.Spruce N32E 14.4' mrkd "1/4S NBT"
4" twin Maple N80W 39.7' do
7" W.Spruce N72E 14.75' do
Bearings are magnetic.



Signed by Stephan J. Szyszkoski Date 10/26/2010
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources and Environment, Forest Management Division