

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 46N R 10W	D3
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 05/20/2010 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a  
Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D3) Quarter corner common to Sections 5 and 8. 1853 - Correctional survey of T46N-R10W performed by  
Geo.H.Cannon, Deputy Surveyor. Set Qr. Section post. Hemlock 20" N39E 8 links, Hemlock 10" S36W 14  
links. 1957 - Corner remonumented in the 1853 position by Billy D. Buckler RLS. Mr. Buckler  
recovered the two Hemlock BTs and remonumented the corner at record bearing and distance from them.  
Set 1" pipe with 4" brass cap. 13" W.Pine N82E 121 links, 8" W.Spruce N76W 43 links.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D3) Found the 1957 monument in good condition and at record bearing and distance from the 1957 NBT  
W.Pine NE, in good condition. The NBT W.Spruce NW was not recovered. The original BT Hemlock N39E 8  
links is not apparent. The original BT Hemlock S36W 14 links is a rotted stump with no markings  
visible, at record bearing and distance.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D3) Fd. 1"ID I.pipe with 4" brass MI Dept. of  
Conservation cap.  
Set measuring nail with MDNR tag in the side of:  
11" W.Pine S08E 7.7' mrkd "1/4S NBT"  
10" W.Pine S54W 32.15' do  
6" Maple N63E 9.6' do  
5" B.Spruce N02W 6.5' do  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 10/26/2010

For the Michigan Department of Natural Resources and Environment, Forest Management Division

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975  
Revised Jan., 1983