

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

<u>Luce</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 10W	D11
	T	R
	T	R
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 10/26/2011 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established,  
monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D11) Quarter corner common to Sections 29 and 32. 1973 - Reestablished by Billy D. Buckler RLS  
midway and on line between Section corners. Set 1" pipe with 4" aluminum cap at the corner. 6"  
Maple N12E 8.1', 8" Maple S81.5E 30.8'. Mr. Buckler states that no evidence of the original corner  
was found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(D11) Found the 1973 monument in good condition and at record bearing and distance from the 1973  
witnesses, both now dead and down. Verified the position of the monument with respect to Section  
corners C11 2693.75' west and E11 2693.03' east, the monument being 0.18' south of a straight line  
between them. I accepted the monument as a careful and faithful reestablishment of the position of  
the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(D11) Fd. 1"ID I.pipe with 4" alum. MI Dept.  
of Conservation cap.  
Set measuring nail with MDNR tag in the side of:  
11" Maple N11W 16.4' mrkd "1/4S NBT"  
9" Maple S68W 13.3' do  
10" Maple S21E 18.65' do  
9" Sugar S75E 40.5' do  
Bearings are magnetic.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 02/14/2012

For the Michigan Department of Natural Resources, Forest Resources Division