

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Luce	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 48N R 11W C1	
	T 49N R 11W C13 (same corner)	
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Stephan J. Szyszkoski, in a field survey on 07/08/2008 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Section corner common to Sections 5-6 T48N-R11W and Sections 31-32 T49N-R11W. 1841 - Established by John Burt, Deputy Surveyor: Set post. Maple 5" N15E 20 links, Beech 10" N35W 28 links. 1958 - Record by Billy D. Buckler RLS states: "This corner was replaced as set by Marcus Schaaf, in intersection of firelanes N-E. Found 2" iron pipe in place. Recent bulldozing in area has removed original witnesses. Corner was placed and witnessed on 10 June 1958". 13" W.Pine N46W 46 links, 15" W.Pine S7E 31 links, 13" W.Pine N40E 57.5 links. 1979 - Remonumented by Billy D. Buckler RLS in the 1958 position: "Found 1" pipe with cap and a 2" pipe with concrete at edge of road. Both have been removed by logging traffic. Buried a 36" "t" iron in firelane intersection. Bearings marked 6-10-1958 still in good condition".

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found the 1979 "t" iron in good condition and at record bearing and distance from the 1958 witnesses, all in good condition with overgrown blazes. Accepted the monument as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found "t" iron, buried in firelane intersection.
Set measuring nail with MDNR tag in the side of:
15" W.Pine N46E 38.33' mrkd "S32" 1958 NBT
22" W.Pine S04E 21.0' "S5" do
18" W.Pine N50W 30.3' "S31" do
18" W.Pine S41W 51.65' mrkd "S6 NBT"
Bearings are magnetic.



Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 02/17/2009

For the Michigan Department of Natural Resources, Office of Land and Facilities

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

Revised May 14, 1975

Revised Jan., 1983

Revised Oct., 1995