

9.

**Corner Code #**

(County)

T1N R3E

M-6

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S T R

## 5. Private Claims

JULY 14, 1997

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

GLO SURVEY DATED APRIL 15, 1825 BY S SIBLEY, DS, AND NONE OF THE GLO WITNESSES REMAIN  
GLO WITNESSES: WO 7"-N14W-25 LKS  
BO 12"-S19W-57 LKS

ADDITIONAL DATA ON REAR OF SHEET

FOUND 1/2" I. ROD WITH M & G CAP # 14762 ABOUT 1.5' SOUTH OF E-W FENCE LINE

## SURVEY & REMONUMENTATION

FEB 24 1998

## SECTION

M-6: E 1/4 COR. SEC. 13 T1N-R3E UNADILLA TWP. LIV. CO. MI, RESET POINT WITH 1 1/4" X 36"  
I. PIPE AT +0.5' WITH LIV. CO. REMON BRASS CAP ON TOP  
N25E-25.52'-SP & TAG WQ/S 4" OAK  
N54E-35.07'-SP & TAG SE/S 5" OAK  
N85E-10.52'-SP & TAG S/S 8" CHERRY  
N75W-8.40'-SP & TAG S/S 8" CHERRY  
NORTH-1.5'-E-W FENCE LINE  
NORTH-0.4'-CARSONITE POST  
NORTH 2.64 FEET TO PUTNAM COR.

Date JULY 14, 1997

Surveyor's Michigan License No. 14762



**P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY**

PEER GROUP ON 3/19/97 CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS JAN 28 1971

REVISÉD MAY 14, 1975

REVISÉD JAN., 1983


REVISÉD OCT., 1905

## CORNER SUMMARY

M-6: EAST 1/4 COR. SEC. 13 T1N-R3E, UNADILLA TWP. LIV. CO. MI.

GLO SURVEY DATED 4/15/1825 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.

IN 1956 L MUNSELL DUG AND FOUND OLD POST AT W 1/4 COR. SEC. 18 PUTNAM TWP. AND SET A BROKEN "T" FENCE POST 4' LONG FOR THE W 1/4 COR. SEC. 18 PUTNAM TWP. IN 1972 MUNSELL-GARLOCK FOUND THE BROKEN "T" FENCE POST FOR W. 1/4 COR. SEC. 18 (WITNESSES FIT) AND SET THE E 1/4 COR. SEC. 13 UNADILLA AT GLO JOG TO THE SOUTH OF 2.64 FEET, COR. SET WITH A 1/2" I. ROD W/CAP. LATER IN 1972 C WILSON FOUND THE M-G IRON, BUT CALLED IT AN I. PIPE, BENTON SAID HE ALSO FOUND AN I. PIPE (DATE UNKNOWN). BOSS IN 1974, 1978 AND 1991 FOUND THE M-G 1/2" I. ROD W/M-G CAP AND WE FOUND MY 1972 1/2" I. ROD WITH M-G CAP IN 1997 REMON SURVEY, REMAINING WITNESSES BY ALL SURVEYORS CHECK WITH WHAT WE FOUND. WE MEASURED NORTH 2668.44 FEET TO M-5 AND WE MEASURED 2669.11 IN OUR 1972 SURVEY. SOUTH WE MEASURED 2615.87 FEET TO THE I. PIPE FOUND IN THE CENTERLINE OF THE OLD RAILROAD GRADE, BOSS ENGR HAD 2616.02 FEET. M-6 WAS FOUND 1.5 FEET SOUTH OF AN EAST-WEST FENCE LINE AND THE SITE IS POOR FOR GPS. RECOMMEND WE USE THE FOUND 1/2" I. ROD WITH CAP AS THE CORRECT CORNER.



CHARLES E. GARLOCK  
PS 14762  
UNA97M6

