

**SURVEY &  
REMONUMENTATION**

FEB 26 2001

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

**FILED**

For corners in

LIVINGSTON  
(County)

Located in:

Corner Code #

1. Public Land Survey

T 1N R 3E I-05

T    R   

T    R   

T    R   

2. Property Controlling  
in Section

S    T    R   

S    T    R   

3. Miscellaneous  
Property in Sec.

S    T    R   

S    T    R   

4. Lot No.           , Recorded Plat                                   

5. Private Claims   

I, DARRELL D. HUGHES, in a field survey on October 12,, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

A. Description of original monument and accessories and/or subsequent restoration:

**GLO:** 1825, Sylvester Sibley, Deputy Surveyor  
Black Oak 7 inch diameter, bears South 46 degrees East, 11 links  
Hickory 9 inch diameter, bears North 57 degrees West, 33 links

**UNADILLA TWP.**

\* ADDITIONAL HISTORICAL INFORMATION ON BACK OF SHEET

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4 inch iron pipe

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**I-05, T1N, R3E, UNADILLA,** replaced existing corner with 1-1/4" x 36" iron pipe, affixed with 2" diameter brass cap, stamped "Livingston Co. Monumentation Corner, P.S. 19834," and is accepted as a careful and faithful reestablishment of the position of the original corner.

008 DEG. 29.45' SET NAIL/TAG W/S 30" OAK


060 DEG. 41.63' SET NAIL/TAG SE/S 36" OAK

175 DEG. 141.99' SET NAIL/TAG W/S 38" OAK

292 DEG. 100.32' SET NAIL/TAG S/S 8" SPRUCE

**PA. 345 1990, APPROVED BY LIVINGSTON COUNTY**  
**PEER GROUP ON** 9-6-00 **CO. REP** Set

Signed by



Date October 12, 2000

Surveyor's Michigan License No. 19834