

SURVEY &  
REMONUMENTATION

FEB 26 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON Located In: Corner Code #  
(County)  
1. Public Land Survey T 1 N R 4 E F-07  
T R  
T R  
T R  
2. Property Controlling S T R  
in Section S T R  
3. Miscellaneous S T R  
Property in Sec. S T R

2000 SEP 28 1 A 9 18

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC #1277m

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JACK K. SMITH, in a field survey on AUGUST 25, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1825 JOSEPH WAMPLER SET POST  
BLACK OAK 5" N38°E 9.24'  
BLACK OAK 6" S15°E 14.52'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

THE EXISTING CORNER IS A 1/2" REROD. THIS APPEARS TO BE THE ONLY CORNER USED SINCE BEFORE 1979.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-07 SOUTH 1/4 CORNER SECTION 16, T1N, R4E, PUTNAM TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:  
SET 1 1/4" x 36" STEEL PIPE WITH LIVINGSTON COUNTY REMONUMENTATION BRASS CAP STAMPED SURVEYOR #35999 IN PLACE OF 1/2" REROD.

N5°E SPIKE AND REMON TAG ON WEST SIDE OF 12" CHERRY 29.18'  
NORTH SPIKE AND REMON TAG ON WEST SIDE OF 8" OAK 33.69'  
S5°E SPIKE AND REMON TAG ON WEST SIDE OF 14" APPLE 31.41'  
N80°E SPIKE AND REMON TAG ON EAST SIDE OF 4" OAK 56.16'  
N75°E SPIKE AND TAG ON NORTH OF RR TIE POST 1.20'

Signed by

Date 9-15-2000



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

PEER GROUP ON 2-2-2000 CO. REP JED

Surveyor's Michigan License No. 35999