

MAR 17 2000

FILED

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
LIVINGSTON
(County)

Located in: HAMBURG Corner Code #

9

1999 NOV 22 A 11:08

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

LSC#1114m

Register of Deeds Stamp and File Number

1. Public Land Survey T 1N R 5E C-10
T R
T R
T R
2. Property Controlling S T R
In Section S T R
3. Miscellaneous S T R
Property In Sec. S T R
4. Lot No. , Recorded Plat
5. Private Claims

I, Bryan L. Boss, in a field survey on 10-12-99,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

SET 1/2 MILE POST
PIN OAK 13" S55°E 0.56CH
WHITE OAK 12" N75°W 0.57CH

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


FOUND 1 1/2" IRON PIPE 1 FT. WEST OF FENCE
7" ABOVE GROUND

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1 1/4" X 36" PIPE WITH BRASS CAP STAMPED
"LIVINGSTON COUNTY REMONUMENTATION
CORNER"
N25°W 17.88' SET REMON NAIL & TAG E/S 24" RED
OAK
EAST 31.86' SET REMON NAIL & TAG N/S 26" RED
OAK
S75°W 22.14' SET REMON NAIL & TAG N/S 8" RED
OAK
SOUTH 21.75' SET REMON NAIL & TAG W/S 48"
RED OAK

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 8 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 6 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY
PEER GROUP ON 6-16-99 CO. REP JED



Signed by Bryan L. Boss

Date NOV. 10, 1999

Surveyor's Michigan License No. 29238