

9-

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For Corners in HAMBURG TWP.

LIVINGSTON (COUNTY)	Located In	Corner Code #
1. Public Land Survey	T1N R5E	X6
	T__ R__	
	T__ R__	
	T__ R__	
2. Property Controlling in Section	S__ T__ R__	
	S__ T__ R__	
3. Miscellaneous Property in Sec.	S13 T1N R5E	001
	S13 T1N R5E	002
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

1996 DEC 19 A 11:28

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C.#644m

REGISTER OF DEEDS STAMP & FILE NUMBER

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, **BRYAN L. BOSS** in a field survey on **NOVEMBER 11, 1996**, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

40 CHAINS 1/2 MILE IN LAKE.

THIS CORNER IS IN WOLFE LAKE.

B. Description of corner evidence found and/or applied in restoring or reestablishing corner:

001:

A WITNESS MONUMENT 964.06 FEET EAST OF K-6 ON STRAIGHT LINE WITH THE ESTABLISHED 1/8 CORNER IN CENTERLINE OF HAMBURG ROAD ON HIGH GROUND AT EDGE OF MARSH 370.00 FEET WEST OF THE 1/8 CORNER.

002:

A WITNESS MONUMENT 1069.78 FEET SOUTH OF K-6 AT INTERSECTION OF NORTH LINE OF UNIT 47 OF "SOLITUDE POINTE" SITE CONDOMINIUM AND THE WEST LINE OF SECTION 13.

C. Description of monument for corner and accessories established to perpetuate location the position of the corner:

001:

SET 1" X 36" PIPE WITH BRASS CAP STAMPED
"LIVINGSTON COUNTY REMONUMENTATION WITNESS"

15° E NAIL & TAG EAST SIDE 6" TRI CEDAR 116.50'
75° E NAIL & TAG SOUTH SIDE 8" CEDAR 29.96'
85° W NAIL & TAG SOUTH SIDE 24" WALNUT 5.45'
80° W NAIL & TAG SOUTH SIDE 10" TRI CHERRY 24.78'


002:

SET 1" X 36" PIPE WITH BRASS CAP STAMPED
"LIVINGSTON COUNTY REMONUMENTATION WITNESS"

N 10° E NAIL & TAG EAST SIDE 10" CHERRY 15.13'
N 60° E NAIL & TAG SOUTH SIDE 10" TWIN OAK 33.18'
N 10° E NAIL & TAG WEST SIDE 18" PINE 103.45'
N 15° W NAIL & TAG NORTHEAST SIDE 8" SASSAFRAS 13.14'
NORTH EDGE OF SW 1/4 SEC 20, T2N, R5E, S13

Signed by Bryan L. Boss
Surveyor's Michigan License No. 29238

Date 12-19-96



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

PFER GROUP ON 10-2-96 CO. REP JED