

FILED

DEC 29 11 25 AM '93

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

For corners in

Livingston (County)	Located In:	Corner Code #
1. Public Land Survey	T 1N R 6E	M-1
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

L.S.C. #177m

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Bryan Boss, in a field survey on December 20, 1993,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO Witness

W. Oak 12" in Dia. N84°E 1.18 Lks.

B. Oak 15" in Dia. N27°W 1.83 Lks.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

SURVEY &
REMONUMENTATION

1993

COMMISSION

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" Bar

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Set with 1 1/4" x 36" Iron Pipe with Brass
Cap (Livingston County Monument Corner)

N30°W 43.10' Spike E/Side Twin 16" Oak
N60°E 33.95' Spike S/Side 22" Walnut
East 32.96' Spike N/Side 14" Walnut
S45°E 40.36' Spike W/Side 42" Walnut

Approved by Livingston Co.
Monumentation Peer Group
on September 15, 1993

Signed by Bryan L. Boss Date December 28, 1993

Surveyor's Michigan License No. 29238



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983