

SURVEY &  
REMONUMENTATION

FEB 26 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON Located In: Corner Code #  
(County)

1. Public Land Survey T 2 N R 4 E E-08  
T R  
T R  
T R

2. Property Controlling S T R  
in Section S T R

3. Miscellaneous S T R  
Property in Sec. S T R

FILED

2000 NOV -8 A 9:43

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC #1346 m

9- Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, JACK K SMITH, in a field survey on AUGUST 4, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1825 SIBLEY SET POST  
TAMARACK 10" N40° E 77.22'  
WHITE OAK 12" S21 1/2° W 78.54'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

THE EXISTING CORNER IS A 1/2" REROD ON THE CENTER LINE OF COON LAKE ROAD ON THE BACKSIDE OF A HILL. THE CORNER LIES APPROXIMATELY 1320' EASTERLY OF THE INTERSECTION OF COON LAKE ROAD AND CEDAR LAKE ROAD. THERE IS A FENCE LINE TO THE NORTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


E-08 WEST 1/4 CORNER SECTION 21, T2N, R4E, MARION TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:  
RESET FOUND 1/2" REROD WITH 1 1/4" X 36" STEEL PIPE WITH BREAK-OFF SECTION AND LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 IN MONUMENT BOX.

N30°W SPIKE AND REMON. WITNESS TAG IN EAST SIDE OF MULTI 10" APPLE 52.36'  
N40°E CENTER OF 6" CHINESE LOCUST 157.10'  
S80°W SPIKE AND REMON. WITNESS TAG IN NW SIDE OF UTILITY POLE 105.93'  
N60°W SPIKE AND REMON. WITNESS TAG IN EAST SIDE OF MULTI 10" APPLE 81.00'

Signed by

Date 10-26-2000

Surveyor's Michigan License No. 35999



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS AND MAPPING  
REVISED MAY 14, 1975 REVISED JAN., 1983

REVISED OCT., 1995

P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY  
PEER GROUP ON 7-19-2000 CO. REP JED