

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in
LIVINGSTON
(County)

Located in: GENOA

Corner Code #

1999 NOV 22 A 11:07

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

1. Public Land Survey T 2N R 5E C-10
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

ISC# 1099m
Register of Deeds Stamp and File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Bryan L. Boss, in a field survey on JUNE 25, 1999

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefor as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:

SET POST
30" W. OAK N86°W 1.82 CHAINS
30" W. OAK N84 1/2°E 2.11 CHAINS

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON ROD, FENCES RUN NORTH, SOUTH, EAST, & WEST.


- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 1 1/4" X 36" PIPE WITH BRASS CAP STAMPED
"LIVINGSTON COUNTY MONUMENTATION
CORNER".
N50°E 25.00' SET REMON NAIL & TAG NW/S 14"
OAK
DUE SOUTH 25.50' SET REMON NAIL & TAG E/S
TWIN 24" OAK
DUE WEST 19.95' SET REMON NAIL & TAG NE/S
18" POPLAR
N20°W 6.39' SET REMON NAIL & TAG W/S 22" OAK

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

PA. 345 1990, APPROVED BY LIVINGSTON COUNTY

DEED GROUP ON 5-19-99, CO. REP JED



Signed by Bryan L. Boss

Date Nov. 9, 1999

Surveyor's Michigan License No. 29238