

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Livingston
(County)

Located in:

Corner Code ##

2N 6E K-11

1. Public Land Survey

T R
T R
T R
T R

Seg. 2 pm

2. Property Controlling
in Section

S T R
S T R

3. Miscellaneous
Property in Sec.

S T R
S T R

4. Lot No. , Recorded Plat

5. Private Claims

FILED
JUN 14 8 32 AM '94
NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI
48843

L.S.C.# 197m

Register of Deeds Stamp & File Number

Bryan Boss

December 20

93

I, in a field survey on , 19 ,
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the
current manual of survey instructions of the United States Department of the Interior, Bureau of Land
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a
Court of Law; established, re-established, monumented, re-monumented, recovered, found as
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Surveyed by Sylvester Sibley - 1823

Witnesses: White Oak 12 in. S73W 2.27
Tammarak 10 in. Dia. N49E 2.17

Additional information on back.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Rerod in Centerline Kensington Road (Asphalt)

SURVEY &
REMONUMENTATION


JAN 19 1999

SECTION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" x 30" Iron Rod and Raised with
1 1/4" x 36" I. Pipe with Brass Cap Marked
Livingston Co. Monument Corner in Monument Box

N30°W 82.35' Spike E/Side Willow
East 31.24' Spike S/Side Power Pole
West 32.75' Top Fence Post
S30°E 93.0' Spike W/Side 6" Elm



Signed by *Bryan L. Boss*

Date June 8, 1994

Surveyor's Michigan License No. 29238