

MAR 17 2000

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

LIVINGSTON
(County)

Located In:

Corner Code #

1. Public Land Survey

T3N R4E

K-05

T___ R___

T___ R___

T___ R___

T___ R___

2. Property Controlling
in Section

S___

T___ R___

S___

T___ R___

3. Miscellaneous
Property in Sec.

S___

T___ R___

S___

T___ R___

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

1999 MAY 21 A 9:22

NANCY HAVILAND
REGISTER OF DEEDS
LIVINGSTON COUNTY, MI.
48843

L.S.C. #1009m

Register of Deeds Stamp & File Number

I, JACK K SMITH, in a field survey on APRIL 30, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2													
3													
4													
5													
6													
7													
8													
9													
10													
11													
12													
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO 1825 SIBLEY SET POST
BLACK OAK 26 N 40° W 9.9'
WHITE OAK 15 S 65° E 34.3'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND BOAT SPIKE IN MONUMENT BOX FROM PREVIOUS WITNESSES. THIS POSITION IS THE ONLY ONE THAT APPEARS TO HAVE BEEN USED.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-05 CORNER COMMON TO SECTIONS 11, 12, 13 AND 14, T3N, R4E, HOWELL TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN:

SET 1 1/4" X 36" STEEL PIPE WITH 6" BREAK OFF SECTION AND LIVINGSTON COUNTY REMONUMENTATION BRASS CAP WITH SURVEYOR #35999 IN MONUMENT BOX 3 FEET EAST OF CENTER LINE OF OAK GROVE ROAD.

N60°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 15" CHERRY
N40°W NAIL WITH LIVINGSTON COUNTY REMON TAG IN NORTH SIDE 12" LOCUST
S80°E NAIL WITH LIVINGSTON COUNTY REMON TAG IN SOUTH SIDE 12" CHERRY
N10°W CENTER LINE OF 3" SPRUCE

67.66'

62.43'

41.97'


129.35'

Signed by

Date

5-11-1999

Surveyor's Michigan License No. 35999



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

PEER GROUP ON 4-7-1999 CO. REP LED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 21
REVISED MAY 14, 1975
REVISED JAN., 1983
REVISED OCT., 1995