

# SURVEY & REMONUMENTATION

FEB 25 1999

## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in **SECTION**  
**LIVINGSTON**  
(County)

Located in:

Corner Code #

1. Public Land Survey

T 3N R 6E H7  
T R  
T R  
T R  
S T R  
S T R  
S T R  
S T R

2. Property Controlling  
in Section

3. Miscellaneous  
Property in Sec.

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

1998 OCT 20 P 1:22

NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI.  
48843

LSC933M

Register of Deeds Stamp & File Number

I, MARY BARNWELL, in a field survey on AUG. 20, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO SURVEY DATED MAY 24, 1823 BY S SIBLEY AND NONE OF THE GLO WITNESSES REMAIN.  
GLO WITNESSES: SUGAR 14'-S72W-8.58'  
LYNN-S68E-6.60'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND 1/2" I. ROD ABOUT 6' NORTH OF EAST-WEST ROAD C/L


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
H7: S 1/4 CORNER SECTION 15 T3N-R6E HARTLAND TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN  
REPLACED FOUND 1/2" I. ROD WITH 1 1/4" X 36" BREAKAWAY PIPE WITH LIVINGSTON COUNTY  
REMON. BRASS CAP ON TOP.  
WEST-16.50'-BOAT SPIKE FOR C/L ROAD EASEMENT TO THE SOUTH.  
S15E-78.26'-SP & TAG W/S OF 5LMULTI-WILLOWS  
S30E-73.94'-SP & TAG W/S 8" ELM  
S45W-52.06'-SP & TAG W/S 12" OAK  
N45W-37.68'-SP & TAG W/S WOOD POST WEST OF DRIVEWAY.  
SOUTH-33.00'-FOUND IRON

Signed by

Surveyor's Michigan License No.

33971

Date AUGUST 21, 1998



P.A. 345 1990, APPROVED BY LIVINGSTON COUNTY

DEED GROUP ON 8-5-98, CO. REP JED

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1985