

1993

## COMMISSION

## LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

LIVINGSTON

(County)

Located In:

Corner Code -#

1. Public Land Survey T 4N R 4E K-12  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

I, Donald G. Richards, in a field survey on October 19, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

## A. Description of original monument and accessories and/or subsequent restoration:

Sylvester Sibley, June 9th, 1823  
Black Ash 14 N 89 1/2 W 32  
Black Ash 12 S 72 E 25

## B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found bolt in monument box  
(see reverse side for research and investigation summary)

## C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Re-set with 1 1/4" x 36" iron pipe w/brass cap stamped "Livingston County Remonumentation Corner" in Monument Box  
S 45 W 52.25' nail/LCWT\* in E face 16" Willow  
N 50 W 48.93' nail/LCWT in S face 17" Poplar  
N 40 E 57.08' nail/LCWT in SE face 6" Elm  
EAST 41.14' nail/LCWT in S face 6" Poplar  
(\* Livingston County Witness Tag)

Signed by DONALD G. RICHARDS

Date December 10, 1993

Surveyor's Michigan License No. 24614

APPROVED by Livingston County Monumentation Peer Group 11-23-93


FILED

DEC 22 9 25 AM '93  
NANCY HAVILAND  
REGISTER OF DEEDS  
LIVINGSTON COUNTY, MI  
48843

L.S.C.# 68m

Register of Deeds Stamp &amp; File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		19		20		21		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



COHOCTAH K-12

Deputy Surveyor Sylvester Sibley set a wood post to establish this point on June 9th, 1823.

Information furnished by C.E. Garlock identifies the corner material as a 1/4" x 16" square iron in 1966. Later surveys by Boss in 1978, 1980, and 1987 identify a 1/2" Iron rod in monument box. However, in Boss'90 the corner is a found bolt in monument box.

On October 19, 1993, fieldcrews recovered a bolt in monument box, consistent with the most recent surveys by Boss'90. Its position relative to corners K-11 and K-12 is substantially as indicated in surveys by Boss'78 and '90.

Donald G. Richards, PS 24614  
November 18, 1993