## LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

Livingston		Located In:	Corner Code ##	
	(County)			
1.	Public Land Survey	T <u>4</u> N R <u>6</u> E T <u> </u>	F=13	
2.	Property Controlling	T R S T R		
	in Section	S T R	,,	
3.	Miscellaneous Property in Sec.	S T R S T R		
4.	Lot No , I	Recorded Plat		

For corners in

5 Private Claims

\_ , 19<sup>95</sup>

Edward E. Anderson in a field survey on\_ June 16, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G.L.O. notes dated: April 5, 1823 G.L.O. Witnesses: W. Oak 20" S27°W 56 Lks B. Oak 18" N18°E 7 Lks

JUL 14 9 45 AH 195 NANCY HAVILAND RECISTER OF DEEDS LIVINGSTON COUNTY. HI

48843

FILED

L.S.C.#407m **Register of Deeds Stamp & File Number** 



Additional historical data on back B. Description of corner evidence found and/or method applied in restoring or reestablishing corner.

Found 1/2" iron. Fit witnesses by Albright

provide a straight · • •

CCT & J 895

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

F-13	<u>S 1/4 Cor. SE</u>	<u>C. 33 T4N-F</u>	16E			
-	Set 1 1/4" x in cente	36" Breakawa erline Parsha	y iron pipe wi llville Road	ith brass c	ap (Liv. Co. Mon. C	or.)
e Constantino de Cons	N54°E 51.22'	spike W/S 24	" Hickory			
	S56°E 45.32'			-		
	S45°W 28.80'				L 345 1990, APPROVED BY	LNINGSTON COUNTY
	N52°W 60.28'	Spike S/S 24	" Apple		1 200 1000 107/95	AN BED JED
			TE OF MICH	Salty PE	R GROUP ON <u>677/95</u>	
, • ;		$\neg 0$	ANDERSON	! <b>\</b> * }		
Signed by	C. Cla	and and the	ENGINEER		<u>July 5, 1995</u>	
•	chigan License No.	11495	NO. NO. T1295 NO. T1295 NO. NO.		FORM APPROYED BY MICHIGAN STATE BO	ARD OF LAND SURVEYORS, JAN. 28, 1971 Revised May 14, 1975 , Revised Jan., 1983

FERR CHORD ON MANAGEMENT OF SER AND SER

P.A. 244 1632, APPROVED BY LIVERSDEEN COUNTY



EDWARD E. ANDERSON, P.S., P.E. RICHARD F. FRANK, P.S. BRIAN R. SHALTZ, C.S.T. Members of: Michigan Society of Professional Surveyors American Congress on Surveying and Mapping American Society of Civil Engineers

(313) 629-8974

FAX (313) 629-9069

401 S. Leroy St. Fenton, Michigan 48430-2164

SUMMARY

May 2, 1995

## F-13 S. 1/4 CORNER OF SECTION 33, T4N-R6E, TYRONE TOWNSHIP, LIVINGSTON COUNTY, MICHIGAN.

Found 1/2" iron in centerline of Parshallville Road (gravel)

Checked and measured to witnesses we found. Found all of Albright witnesses and they checked. We looked for the N 1/4 corner of Section 4, T3N-R6E, and did not find any iron; however, there is an old fence line running to the south, which if extended north to the intersection of the north line of said Section 4, falls approximately 1/2 way between the NE and the NW corners of said Section 4 and said intersection falls 21' - to the east of the South 1/4 corner of said Section 33, which matches close to the job of 22.77' when subtracting the G.L.O. jogs at the NE and NW corners of said Section 4 and dividing by two. See sheet 8 of this dossier.

Distance from the S 1/4 corner to the SE corner of said Section 33 is 2653.68'. on Albright survey, page 9 this dossier.

Distance from the S 1/4 corner to the S.W. corner of said Section 33 is 2653.68' on Albright survey, pages 9 thru-12 this dossier.

Made a clean sweep of immediate area and found no additional corners or irons.

Gravel roads running east and west. Road rises to the west and falls to the east.

Terrain is open to the south and farm buildings to the north.

Old fence and tree line to the north.

Poor location for G.P.S.

Came to the conclusion that the 1/2" iron we found is the correct South 1/4 corner of siad Section 33.

NAM ANDERS ÷. SURVEYOR Edward E. Anderson ENGINEER P.S.#11495 NO 11495 Surveyor & fical's