

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Mackinac

(County)

Located in:

Corner Code #

1. Public Land Survey

T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_

2. Property Controlling  
in Section

S\_31 T\_42N R\_12W 11  
S\_31 T\_42N R\_12W 10

3. Miscellaneous  
Property in Sec.

S\_\_\_ T\_\_\_ R\_\_\_  
S\_\_\_ T\_\_\_ R\_\_\_

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

10 May 24 2006

11 Apr 25 2006

I, Stephan J. Szyszkoski, in a field survey on \_\_\_\_\_, 19\_\_\_\_ do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

(11-Sec. 31) Southwest 1/16 corner, Section 31. Not established in the original survey. Found no subsequent record.  
(10-Sec. 31) South 1/16 corner between Section 31 T42N-R12W and Section 36 T42N-R13W. Not established in the original survey. 1928 - Established during a resurvey of the Range line for Manistique Line and Stone Co. under direction of the Department of Conservation. Field notes show a 1"IDx4 ft. long iron pipe placed midway and on line between Township corner 1351.04' south and Quarter corner 1351.04' north. 12" W.Pine S19-10W 82.3' to C., 8" Norway Pine S04-20W 130.00, 6" Norway Pine N89-40W 170.00, 12" Hemlock N69-30W 32.4'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(11-Sec. 31) Established the corner at the intersection of straight lines connecting opposite 1/16 corners.  
(10-Sec. 31) Recovered a 1"ID iron pipe, length unknown, in good condition, 0.04' West and 0.28' north of the 1928 record position. I found the Twp. corner 1350.81' south and the 1/4 corner 1350.25' north. Accepted same as a careful and faithful determination of the position of the corner. Drove a plastic cap stamped "MICH DNR PS33986" into the pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(11) Set 1"IDx36" I.pipe with 4" alum. MDNR cap. Set measuring nails in:  
14" Maple N05W 21.9' mrkd "SW1/16 BT"  
14" Hemlock N57E 18.95' do  
11" Hemlock S22E 75.25' do  
9" Maple S15W 68.9' do  
Bearings are magnetic. Distances are to nail with tag.

(10) Found 1" pipe, placed plastic cap in it. Set measuring nails in:  
10" W.Pine N63W 13.22' mrkd "S1/16 BT"  
10" R.Pine S24W 28.07' do  
6" W.Pine S60E 20.53' do  
6" W.Pine N12W 7.0' do  
Bearings are magnetic. Distances are to nail with tag.



Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 8/9/06