

1993

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

Manistee  
 (County)

Located In:

Corner Code #

1. Public Land Survey

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T 22N R 15W2. Property Controlling  
in SectionS 19 T 22N R 14W

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

REGISTER'S OFFICE  
 MANISTEE COUNTY

FEB 2 1993

NO. 93-39 AT 9:00 AM  
 REGISTER OF DEEDS

Register of Deeds Stamp &amp; File Number

I, Robert F. Mitchell, in a field survey on August, 19 92,

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Indian Reserve Corner on West line of Section 19; This corner was not established during the original U.S. Survey conducted by J. Brink in 1839. In 1900 J. Millard, Manistee County Surveyor established this corner.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Indian Reserve Corner on West line of Section 19; Found no evidence of Millard's witnesses of 1900 as recorded in Book "B" pp. 54-55 of the Manistee County Surveyor Records. Set a 2" x 30" galvanized pipe with 3" brass cap at proportionate distance between controlling government corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Indian Reserve Corner on West Line of Section 19;  
 Set a 2" x 30" galv. pipe w/ 3" brass cap  
 flush with the ground.

South -  $W\frac{1}{2}$  Corner Sec. 19 - 137.06'  
 S65°E - 6" Black Ash - 44.82'  
 S39°E - 7" Black Ash - 47.22'  
 S05°W - 13" Black Ash - 61.59'  
 S51°W - 6" Black Ash - 34.29'  
 South - carsonite post - 1.0'



Signed by

Date

Surveyor's Michigan License No. 28417

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 11  
 REVISED MAY 14, 11  
 REVISED JAN. 11

ratified by the Manistee  
 County Peer Group pursuant to P.A. 123 of  
 1915, as amended by P.A. 345 of  
 1990, as amended. Date of Peer Review: JAN 4 1993