

SURVEY & REMONUMENTATION

APR 04 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
COUNTY OF MECOSTA
RECEIVED FOR RECORD

For corners in

Mecosta

(County)

Located In:

Aetna Township

Corner Code #

'95 DEC 29 A8:47

1. Public Land Survey Sec 21/ T 13 N R 10 W G-8, 1/4 Corner
22 T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

4. Lot No. Recorded Plat
5. Private Claims

I, William Tingley a field survey on July 25, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1837, Abner VanNess, Deputy Surveyor, GLO Notes

Set Quarter Post

Maple 10" N67°W 4 links
Pine 20" S67°E 5 links

1971, Patrick Salisbury, LCRC, Liber 1, Page 33

Red Fence Post - protruding 1-1/2 feet above ground

White Oak 10" N60°E 4.80 feet
White Pine 14" S23°W 16.00 feet
White Oak 14" S37°E 21.85 feet

1981, Jack Pierson

Angle Iron

Oak 13" N55°E 4.65 feet
Maple 13" S85°W 16.88 feet
Oak 16" S30°E 22.15 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Fence Post from above witnesses

Fence post red in color and 1-1/2 feet above ground.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Remonumentation Corner over Fence Post 1 foot above ground.

Oak 13" N55°E 4.65 feet
Maple 13" S85°W 16.88 feet
Oak 16" (stump) S30°E 22.15 feet
Pine 14" S23°W 16.00 feet

This corner is accepted as a careful and faithful perpetuation of the position of the original corner.

James Brown
REGISTER OF DEEDS


Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

APPROVED BY MECOSTA CO. PEER GROUP
IN ACCORDANCE WITH P.A. 345 of 1990

James H. Knapp
CHAIRMAN

DATE July 27, 1995



Signed by William G. Tingley Date 12-12, 1995

Surveyor's Michigan License No. 30104

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971

REVISED MAY 14, 1976

REVISED JAN., 1983

ADAPTED FOR WORD PROCESSING MARCH, 1993