

L. C 00004, P. 00297

9/11/18

Land Corner Recordation Certificate  
Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Craig W. McVean      Field Survey Date: January 18, 2018  
For corner(s) in: Midland      County

Original Public Land Survey Corner			Corner Code
S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Controlling Corner			Corner Code
S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Corner			Corner Code
S	10	T 14N R 2W	5
S		T	R
S		T	R
S		T	R

Protracted Public Land Survey Corner			Corner Code
S	10	T 14N R 2W	H4
S		T	R
S		T	R
S		T	R

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														1
2	6			5		4		3		2		1		2
3														3
4	7			8		9		10		11		12		4
5														5
6	18			17		16		15		14		13		6
7														7
8	19			20		21		22		23		24		8
9														9
10	30			29		28		27		26		25		10
11														11
12	31			32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

<b>H4</b> – C ¼ Corner Sec. 10, T14N, R2W	<b>5</b> – CN 1/16 Corner Sec. 10, T14N, R2W
- None	- None

**Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner**

**H4** – C ¼ Corner Sec. 10, T14N, R2W –

Set stamped 2" Aluminum Cap on 5/8" x 34" long iron rebar at intersection of ¼ lines per standard BLM procedure. The center of a 10" steel pipe fence corner is N80°24'W 21.5'. The fence is mostly standing barb wire to the West and South. ¼ mile south the fence is 10'± West of the N-S ¼ line. Traced the fence West 1317'± (1338' from 'H4') and a 10" steel pipe fence corner is 30' North of the E-W ¼ line. The fence is standing to the E & S at this point. The fence remains that continues west is barb wire on the ground and wire in some trees. At 2364' west of 'H4' the fence remains are 50'± North of the E-W ¼ line. The fence remains then bend and proceeds to arc to a fallen RR tie corner post near the East ROW of Geneva Road some 32' North of the E-W ¼ line and 32' East of the West section line. The grid distance from 'H4' to 'G4' is 2654.44'. Thus it was concluded that the fence did not represent a valid location of the E-W ¼ line in Section 10.

**5** – CN 1/16 Corner Sec. 10, T14N, R2W –

Set stamped 2" Aluminum Cap on 5/8" x 34" long iron rebar per standard BLM procedure.

**Part C: Field Evidence of Perpetuation or Monumentation of Corner**


**H4** – C ¼ Corner Sec. 10, T14N, R2W –

Stamped 2" Aluminum Cap on 5/8" x 34" long iron rebar. Set Blue Composite Post with Loc. tag 1' NE.  
N55°W 50.05' to set N & T in SW side 18" W. Pine  
North 26.87' to set N & T in E. side 7" W. Pine  
N88°E 10.21' to set N & T in S. side 11" Oak  
S48°W 26.36' to set N & T in SE side 10" W. Oak


**5** – CN 1/16 Corner Sec. 10, T14N, R2W –

Stamped 2" Aluminum Cap on 5/8" x 34" long iron rebar.  
Set Blue Composite Post with loc. tag 1' SE  
East 3.12' to set N & T in N. side 7" R. Maple  
S43°E 32.39' to set N & T in SW side 24" W. Pine  
N86°W 18.93' to set N & T in N. side 5" R. Maple  
N43°E 16.59' to set N & T in NW side 6" Oak





Craig W. McVean



Date

Professional Surveyor's License No.: 39088

Prepared By:

Craig W. McVean

Michigan Dept. of Natural Resources

8015 Mackinaw Trail

Cadillac, Michigan 49601

Land Corner Recordation Certificate

S 10 T 14N R 2W Code H4

S 10 T 14N R 2W Code 5

Page 2 of 2