

L. C 00004, P. 00300

9/11/18

Land Corner Recordation Certificate

Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Craig W. McVean

Field Survey Date: May 14, 2018

For corner(s) in: Midland County

Original Public Land Survey Corner

Corner Code

S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Controlling Corner

Corner Code

S	T	R	
S	T	R	
S	T	R	
S	T	R	

Property Corner

Corner Code

S	10	T	14N	R	2W	3
S	10	T	14N	R	2W	12
S		T		R		
S		T		R		

Protracted Public Land Survey Corner

Corner Code

S	T	R	
S	T	R	
S	T	R	
S	T	R	

	A	B	C	D	E	F	G	H	I	J	K	L	M	
1														1
2	6			5		4		3		2		1		2
3														3
4	7			8		9		10		11		12		4
5														5
6	18			17		16		15		14		13		6
7														7
8	19			20		21		22		23		24		8
9														9
10	30			29		28		27		26		25		10
11														11
12	31			32		33		34		35		36		12
13														13
	A	B	C	D	E	F	G	H	I	J	K	L	M	

Part A: Corner History

3 – N 1/16 corner, common to sections 9 and 10, T14N, R2W

-None

12 – CS 1/16 corner section 10, T14N, R2W

1900's – S. Carroll Drain notes – F.T. Gibbs "Cross N-S 1/4 line sec. 10 at 23 chains north of south line of said section"

2000- Rec. Survey-L. 6, P. 97- K. T. Pomaville (PS#43066) – Set iron & cap 43066.

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

3 – N 1/16 corner common to sections 9 and 10, T14N, R2W-

Set stamped 2" Alum. Cap on 5/8" x 34" iron rebar per standard BLM procedure in N-S gravel road.

12 – CS 1/16 corner section 10, T14N R2W-

Fd. 1/2" x 24" long capped rebar # 43066. N-S barbwire fence is 10' West. 1/2" CIR accepted as the best available evidence of the position of the corner.


Part C: Field Evidence of Perpetuation or Monumentation of Corner

3 – N 1/16 corner common to sections 9 and 10, T14N R2W- Stamped 2" Aluminum Cap on 5/8"x34" long rebar East 33.00 to set 2" Alum. Cap on 5/8" x 34" rebar w/ Blue Composite Post w/ Loc. Tag. West 33.14' to fd. 'T' iron #14769 S56°W 40.31' to set N&T in NW side of power Pole. S55°E 67.44' to set N&T in NE side of 15" Oak

12 – CS 1/16 corner common to sections 9 and 10, T14N R2W

Replaced 1/2"x 24" long CIR # 43066 with stamped 2" Aluminum Cap on 5/8"x 34" long iron rebar N7°W 48.77' to set N&T in west side of 13" Oak S63°E 6.29' to set N&T in south side 7" Poplar S12°W 9.84' to set N&T in east side of 2" W. Oak N74°W 39.46' to set N&T in north side of 6" Oak Add Blue Composite Post w/ Loc. tag 1' NE.





Craig W. McVean

9/10/2018
Date

Professional Surveyor's License No.: 39088

Prepared By:
Craig W. McVean
Michigan Dept. of Natural Resources
8015 Mackinaw Trail
Cadillac, Michigan 49601