

Land Corner Recordation Certificate
Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Craig W. McVean
Field Survey Date: September 9, 2016
For corner(s) in: Midland County

Original Public Land Survey Corner
S T R
S T R
S T R
S T R

Property Controlling Corner
S T R
S T R
S T R
S T R

Property Corner
S 34 T 16N R 1W
S 34 T 16N R 1W
S T R
S T R

Protracted Public Land Survey Corner
S T R
S T R
S T R
S T R

Table with 13 columns (A-M) and 13 rows (1-13). Contains section numbers 1-36. A dot is present in cell H34.

Part A: Corner History

9 - CE 1/16 Section 34, T16N, R1W
-No history

C-N-SE 1/64 - corner of section 34 being the northwest corner of the S 1/2 of the NE 1/4 of the SE 1/4 of Section 34, T16N, R1W.
-No history

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

9 - CE 1/16 corner section 34, T16N, R1W – Set 2" stamped Aluminum cap on 5/8" x 48" long rebar per standard BLM procedure.
S78°W 8.2' to cedar fence post with rotten single strand barbed wire – North and east. Corner falls in leather leaf marsh.

C-N-SE 1/64 – corner of section 34, T16N, R1W, being the northwest corner of the S ½ of the NE ¼ of the SE ¼ Section 34, T16N, R1W- Set 2" stamped Aluminum cap on 5/8" x 34" long rebar per standard BLM procedure.


Part C: Field Evidence of Perpetuation or Monumentation of Corner

9 - CE 1/16 corner section 34, T16N, R1W – Stamped 2" Aluminum cap on 5/8" x 48" long rebar.


Set blue composite post with location tag 1' west
N67°W 8.3' to centerline of 2" White Pine at face blaze
N13°W 29.11' to set nail & tag in east side of 12" White Pine
N57°E 36.43' to set nail & tag in south side twin 16" & 20" White Pine
S13°E 21.4' to centerline 2" White Pine at face blaze

C-N-SE 1/64 – corner of section 34, T16N, R1W, being the northwest corner of the S ½ of the NE ¼ of the SE ¼ Section 34- Stamped 2" Aluminum cap on 5/8" x 34" long rebar.

Set blue composite post with location tag 1' southwest
N48°W 25.14' to set nail & tag in northeast side 13" Oak
N18°E 17.74' to set nail & tag in west side twin 10" Oak
S87°E 46.77' to set nail & tag in north side twin 10" & 16" Red Maple
S03°E 13.38' to set nail & tag in east side 12" Oak



Craig W. McVean



Date

Professional Surveyor's License No.: 39088

Prepared By:
Craig W. McVean
Michigan Dept. of Natural Resources
8015 Mackinaw Trail
Cadillac, Michigan 49601



Land Corner Recordation Certificate
S 34 T16N R1W Code 9
S 34 T16N R1W Code C-N-SE 1/64