

Land Corner Recordation Certificate
Authority: 1970 PA 74, MCL 54.205

Surveyor's Name: Craig W. McVean
Field Survey Date: June 26, 2017
For corner(s) in: Midland County

Original Public Land Survey Corner
S 32 & 33 T 16N R 01W
Corner Code E12

Property Controlling Corner
S T R
S T R
S T R
S T R
Corner Code

Property Corner
S T R
S T R
S T R
S T R
Corner Code

Protracted Public Land Survey Corner
S T R
S T R
S T R
S T R
Corner Code

Table with 13 rows and 13 columns (A-M). Contains section numbers 1-36. A dot is located at the intersection of row 12 and column E.

Part A: Corner History

E12 -1/4 corner common to section 32 & 33, T16N, R1W-
1832 -GLO- H. Parke, A Pine 18" a qr. sec. corner
-1852 - A. Burt - GLO Dependent Resurvey - Set Post in stump of old corner
1) W. Birch 6" S59°W 18 L.
2) W. Pine 18" N32°E 53 L.

Part B: Surveyor's Report on Perpetuation, Restoration, Reestablishment, or Monumentation of Corner

E12 – 1/4 corner common to section 32 & 33, T16N, R1W-


Searched for evidence of two pines stumps that would conform to the GLO record but could only find one in the search area. Also searched for line tree evidence to the south and found several pine stumps that could have been line trees but nothing that would conclusively fit a position for the 1/4 corner in regard to the pine stump found in the search area. Thus set a stamped 4" DNR aluminum cap on a 1" x 36" long galvanized iron pipe by single proportion and holding the record 1852 GLO angle at 'E12' between reestablished positions at 'E13' and 'E11'. Measured grid bearing and distance of S00°08'11"W 2621.25' [South 39.90 (2633.4') -GLO] to 'E13' and N00°31'12"E 2640.29' [N0°23'E 40.19 (2652.54')-GLO] to 'E11'. Measured north 146'+/- 5' to enter marsh vs. GLO calls for leave thicket North 2.1 CH C. SE & NW. Measured south 1702' to bottom of bank of bottomlands and now also being the edge of stream vs. 1709'-GLO. DNR monument is 5'+/- north of low area. DNR monument accepted as a careful and faithful reestablishment of the position of the original corner.

Part C: Field Evidence of Perpetuation or Monumentation of Corner


E12 –1/4 corner common to section 32 & 33, T16N, R1W-

Stamped 4" DNR Aluminum Cap on 1" x 36" long galvanized iron pipe.
Set Blue Composite Post 1' South
S85°W 5.80' to set Nail & Tag (N & T) in N side 4" R. Maple
N17°W 4.20' to set N & T in W side 9" Oak scribed 'XBT'
N52°E 10.18' to set N & T in side of 7" Oak
S55°E 10.08' to set N & T in NE side 4" R. Maple side scribed 'XBT'





Craig W. McVean



Date

Professional Surveyor's License No.: 39088

Prepared By:

Craig W. McVean

Michigan Dept. of Natural Resources

8015 Mackinaw Trail

Cadillac, Michigan 49601