

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 47N R 29W	D7
	T R	(GCDB 240400)
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 06/16/15 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(D7) Quarter corner common to Sections 17 and 20. 1848 - Established by John Burt, Deputy Surveyor, midway and on the Section line between Section corners 40.45 chains east and west. The notes state "Qr. section cor. inaccessible" and the corner is presumed here to have not been monumented. Marquette Co. Rd. Commission field book 653, says that the corner is monumented by a "Post S. edge of Black River". No other record found.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:



(D7) Found no evidence of the original corner position on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2673.46' east and west. The position for the corner falls in the marsh adjacent to the Black River and, being inaccessible, was not monumented. Established two Witness corners, described below, on the Section line 243.20' east and 478.66' west of the corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

W.C. 243.20' east of the corner position.
Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
2" B.Spruce N47°E 11.65' mrkd "X X"
2" Cherry S19°E 13.95' do
2" B.Spruce N22°W 23.35' do
2" B.Spruce N18°W 0.7' do
Set cedar post adjacent.
E= 7926323.214 N= 187210.113 (the W.C.)
This W.C. falls at N. end of beaver dam.

W.C. 478.66' west of the corner position.
Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
4" W.Birch N30°E 16.3' mrkd "WC BT"
Tamarack S54°E 14.3' do
W.Birch S23°W 26.25' do
2" B.Spruce N30°W 16.9' "X X"
Set cedar post adjacent.
E= 7926103.249 N= 187213.121 (the W.C.)

Bearings are magnetic. Coordinates are MCS83 in meters, NAD83(2011) Epoch 2010.00 datum.
Coord. Ref.=NGS PID AA8080: N= 192972.689 m. E= 7925456.741 m.

Signed by Stephan J. Szyszkoski Date 06/23/2015
Surveyor's Michigan License No. 33986

For the Michigan Department of Natural Resources, Forest Resources Division