

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 29W	I8
	T R	(GCDB 500340)
	T R	
2. Property Controlling in Section	S 22 T 48N R 29W	H8
	S T R	(GCDB 440340)
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. , Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 09/22/14 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(I8) Quarter corner common to Sections 22 & 23. 1848 - Established by Wells Burt, Deputy, midway
and on the Section line between Section corners 2634.55' north and south. Set spruce post.
Spruce 10" S45°E 48 links, Fir 6" N53°W 53 links. Found no subsequent record.

(H8) Center of Section 22. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(I8) The original post and accessories were not recovered. Found no evidence of the position of the
original corner on the ground. Reestablished the position for the corner midway and on the Section
line between Section corners 2634.55' north and south. The position also conforms to the 1848 US
record with respect to line calls to Top of ledge 100 feet c.E&W 37.85 chains south and to Stream 10
c.S.W. 22.88 chains north.

(H8) Established the position for the corner at the intersection of straight lines connecting
opposite 1/4 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(I8) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" Maple N03°E 15.3' mrkd "1/4S NBT"
5" Balsam S86°E 8.15' do
6" twin Maple S17°E 15.05' do
7" Maple N75°W 11.3' do
Set sq'd cedar post adjacent.
E= 7930388.152 N= 195972.597

(H8) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
10" W.Birch N01°W 7.4' mrkd "C1/4 BT"
7" B.Spruce S81°E 12.15' do
6" Sugar S13°W 23.0' do
6" Sugar N75°W 18.4' do
Set sq'd cedar post adjacent.
E= 7929586.589 N= 195987.885

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum)
Coord. Ref.=NGS PID AA8080: N= 192972.689 m. E= 7925456.741 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/24/2014

For the Michigan Department of Natural Resources, Forest Resources Division

