

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 30W	F5
	T R	(340500)
	T 48N R 30W	G2
	T R	(400640)
2. Property Controlling in Section	S T R	
	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5			4	3		2		1		
3													
4	7		6			9	10		11		12		
5													
6	18		17			16	15		14		13		
7													
8	19		20			21	22		23		24		
9													
10	30		29			28	27		26		25		
11													
12	31		32			33	34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 07/16/14 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F5) Quarter corner common to Sections 9 and 16. 1848 - Established by Wells Burt, Deputy Surveyor
midway and on the Section line between Section corners 40.20 chains east and west. Set Fir post.
Fir 10" N12°W 7 links, Spruce 12" S38°E 33 links. Found no subsequent record.

(G2) Quarter corner common to Sections 3 and 4. 1848 - Established by Wells Burt, Deputy Surveyor
on the Section line between Section corners 40.00 chains south and 39.21 chains north. Set Fir
post. Y.Birch 22" N65°W 13 links, Maple 8" S7°E 28 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F5) The original post and accessories were not recovered. Found no evidence of the position of the
original corner on the ground. Reestablished the position for the corner midway and on the Section
line between Section corners 2646.99' east and west.

(G2) The original post and accessories were not recovered. Found no acceptable evidence of the
position of the original corner on the ground. Reestablished the position for the corner midway and
on the Section line between Section corners 2606.72' south and 2555.25' north.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F5) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
5" Maple N60°E 12.0' mrkd "1/4S NBT"
4" Spruce S24°W 37.0' do
24" W.Pine S80°W 19.0' do
7" Spruce N10°W 29.6' do
Set sq'd cedar post adjacent.
E= 7918363.611 N= 198464.338

(G2) Set 1"IDx28" I.pipe with 2" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
9" Maple N17°E 36.0' mrkd "1/4S NBT"
8" twin Maple N58°E 29.6' do
18" W.Pine S22°E 4.15' do
4" Balsam N27°W 7.2' do
Set sq'd cedar post adjacent.
E= 7919201.895 N= 200856.340

Bearings are magnetic. Coordinates are MCS83 in meters (NAD83(2011) Datum).
Coord. Ref.=NGS PID AA8080: N= 198400.952 m. E= 7925456.741 m.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 11/12/2014

For the Michigan Department of Natural Resources, Forest Resources Division

