

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Baraga (County)	Located In:	Corner Code #
1. Public Land Survey	T 48N R 32W	B7
	T R	
	T R	
2. Property Controlling in Section	S T 8 T 48N R 32W	7
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 7 05/29/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(B7) Quarter corner common to Sections 18 and 19. 1852 - Established by Guy Carleton, Deputy
Surveyor, on the Section line between Section corners 40.00 chains east and 35.61 chains west. Set
post. Yellow Birch 14" S37E 27 links, Yellow Birch 6" N33W 14 links. Found no subsequent record.

(7-Sec. 8) North 1/16 corner between Sections 8 and 9. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(B7) The original post and accessories were not recovered. Found no evidence of the position of the
original corner on the ground. Reestablished the position for the corner on the Section line between
Section corners 2648.12' east and 2357.48' west, being proportionate to the original record.

(7-Sec. 8) Established the position for the corner midway and on the Section line between Section
corner 1325.59' north and Quarter corner 1325.59' south.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(B7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" Balsam N29E 8.9' mrkd "1/4S NBT"
5" Maple S26E 19.55' do
5" Poplar S44W 7.35' do
5" Maple N55W 1.85' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

(7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
6" B.Spruce N60E 6.0' mrkd "1/16S BT"
5" W.Pine S75E 27.05' do
5" B.Spruce S10W 14.9' do
4" B.Spruce S86W 8.9' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 09/12/2012

For the Michigan Department of Natural Resources, Forest Resources Division

