

1993

COMMISSION

JOB NUMBER: 93300

SHEET NO. : 1-322

For corners in

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

MARQUETTE COUNTY  
MICHIGAN  
RECEIVED FOR RECORD  
1993 DEC 22 PM 4:11

*Patricia R. Morley*  
REGISTERED DEEDS

<u>MARQUETTE</u> (County)		Located In:	Corner Code ##
1. Public Land Survey	T 49N R 25W	MC F/G13	
	T 48N R 25W	MC F/G1	
	T _____ R _____		
	T _____ R _____	#1	
2. Property Controlling in Section	S _____ T _____ R _____		
	S _____ T _____ R _____		
3. Miscellaneous Property in Sec.	S _____ T _____ R _____		
	S _____ T _____ R _____		
4. Lot No. _____	Recorded Plat _____		
5. Private Claims _____			

Liber 1 R.C. Page 10.

Register of Deeds Stamp & File Number

I, GERALD W. CARLSON, in a field survey on Tuesday, November 30, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:


MC F-13: Meander corner East of South Quarter Corner  
Section 33, 1845: William A. Burt's original survey notes  
describe the corner monument as an 8" Y. Pine  
referenced by:  
6" Y. Pine S891/2°W, 49.1

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

1993 - Corner position established at astronomic bearing due East, 601.26 ft. G.L.O. distance from the South 1/4 corner of Section 33, T49N-R25W. A 3/4" diameter iron rebar was grouted into solid rock at this corner position. No G.L.O. evidence found. Corner falls in small plateau approximately 15 ft. above water level on rocky shoreline. Rocky jagged shore to the North, sand beach begins approximately 400-500 ft. to the South. 37 ft. from waters edge at small "V" in rock shoreline. Peer group ratification 11-29-93.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1993 - Set a 3/4" diameter rerod grouted into bedrock capped with the 3 1/4" diameter aluminum tablet Marquette County Survey Monument stamped to identify the corner referenced by nails in:  
3" Red Pine N57W 1.33 ft.  
6" White Pine S79E 12.29 ft.  
16" White Pine S20W 22.40 ft. (gnarled)  
Hilty nail in rock shelf N32E 60.10 ft.  
0.72 ft. above ground.  
Bk. 3, pg. 76



Signed by Gerald W. Carlson

Date 12-22-93

Surveyor's Michigan License No. 24589