

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette	Located In:	Corner Code #
(County)		
1. Public Land Survey	T 50N R 28W	F7
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S 16 T 50N R 28W	4
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 4 09/11/2012 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(F7) Quarter corner common to Sections 16 and 21. 1852 - Established by A.B.Wood, Deputy Surveyor, midway and on the Section line between Section corners 40.00 chains east and west. Set post. Spruce 9" S55W 12 links, Spruce 10" S86E 42 links. July 17, 1947 notes in F.B.601, p.125 Marquette Co. Road Commission state "A squared and dry J.Pine marked app. 1/4 cor. Found no BT's. JJH" Found no subsequent record.

(4-Sec. 16) Northwest 1/16 corner, Section 16. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(F7) The original post and accessories were not recovered. Did not find the dry J.Pine noted in the Rd. Commission notes. Found no acceptable evidence of the position of the original corner on the ground. Reestablished the position for the corner midway and on the Section line between Section corners 2644.86' east and west, being proportionate to the original record.

(4-Sec. 16) Established the position for the corner at the intersection of straight lines connecting opposite 1/16 corners.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(F7) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
14" W.Pine N16E 34.0' mrkd "1/4S NBT"
6" J.Pine N55E 20.15' do
7" R.Pine S18E 33.1' do
8" J.Pine S74W 11.55' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(4) Set 1"IDx32" I.pipe with 4" alum. MDNR cap. Set measuring nail with MDNR tag in the side of:
10" Oak N15E 13.75' mrkd "1/16S BT"
4" W.Pine S44E 6.45' do
10" W.Pine S23W 11.4' do
9" Oak N30W 16.45' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 10/08/2012

For the Michigan Department of Natural Resources, Forest Resources Division

