

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 29W	E6
2. Property Controlling in Section	S 16 T 52N R 29W	11
3. Miscellaneous Property in Sec.		
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		10		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, Stephan J. Szyszkoski, in a field survey on 11 11/10/2010 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E6) Quarter corner common to Sections 16 and 17. 1991 - Corner reestablished by G.C.Van Neste PS
at GLO record bearing and distance north of corner E7. From this position a 1" iron pin was found
122.2' southerly and was not accepted as marking the position of the original corner.

(11-Sec. 16) Southwest 1/16 corner, Section 16. Established in 2001 by G.C.Van Neste PS at the
intersection of straight lines connecting opposite 1/16 corners.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E6) Found a 5/8" dia. rebar with plastic cap #27464 in accord with Mr. Van Neste's measurements.
Accepted same as a careful and faithful reestablishment of the position of the original corner.

(11-Sec. 16) Found a 5/8" dia. rebar with plastic cap #27464 in accord with Mr. Van Neste's
measurements and at the intersection of 1/16 lines. Accepted same as a careful and faithful
determination of the position of the corner. The corner position falls on the west bank of a 1.5'
wide creek and is undercut. Placed boulders adjacent to protect the corner position from further
erosion.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E6) Fd. 5/8" rebar with plastic cap #27464
Set measuring nail with MDNR tag in the side of:
8" twin Maple N27E 11.0' mrkd "1/4S NBT"
7" Maple S23E 10.5' do
6" Maple S22W 5.7' do
4" W.Spruce N40W 10.35' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(11) Fd. 5/8" rebar with plastic cap #27464
Set measuring nail with MDNR tag in the side of:
9" Balsam N55E 44.0' mrkd "1/16S BT"
18" Y.Birch S45W 63.4' do
15" Sugar S70W 74.8' do
16" Hemlock S84W 61.5' do
Set sq'd Cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 02/02/2011

For the Michigan Department of Natural Resources and Environment, Forest Management Division

