

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 29W	E12
	T R	
	T R	
2. Property Controlling in Section	S 17 T 52N R 29W	9
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on 9 03/26/2012 do hereby state  
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2  
above were in conformance with regulations and rules therefore as required in the current manual of survey  
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of  
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with  
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,  
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(E12) Quarter corner common to Sections 32-33. 1846 - Established by Deputy Surveyors Hubbard and  
Ives. Set post. Sugar 10" S56W 35 links, Hemlock 8" N17E 23 links. 1941 - Norman T. Thompson RLS  
field notes state that he found the Hemlock 8" N17E 23 links "OK down", and "Set ced. post New BT at  
1/4 Y.Bir 9" South 10 ft. 10 in."

(9-Sec. 17) East 1/16 corner, Section 17. Not previously monumented.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(E12) The original post and accessories were not recovered. Found and ~~old~~ squared post at the corner  
position with a second old post laying down on the ground, adjacent. Found the 1941 NBT Y. Birch  
South 10.8' with healed blaze facing the corner. No scribing visible. Found Ford Motor Co. location  
poster adjacent indicating 1/4 cor. 32/33. Accepted the standing post as a careful and faithful  
perpetuation of the position of the original corner and replaced it with a new monument as described  
below.

(9-Sec. 17) Established the position for the corner midway and on a straight line between Quarter  
corner 1321.43' east and Center of Section 17 1321.43' west.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(E12) Set 1"IDx32" I. pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
10" Oak N38E 15.75' mrkd "1/4S NBT"  
7" Sugar S32E 17.6' do  
3" W.Spruce S47W 11.9' do  
7" Sugar N30W 28.25' do  
Set sq'd Sugar post adjacent.  
Bearings are magnetic.

(9) Set 1"IDx32" I. pipe with 4" alum. MDNR cap.  
Set measuring nail with MDNR tag in the side of:  
11" Sugar N42E 11.85' mrkd "1/16S BT"  
6" Ironwood S70E 18.4' do  
15" Y.Birch S33W 14.3' do  
10" Sugar N50W 8.7' do  
Set sq'd cedar post adjacent.  
Bearings are magnetic.

Signed by Stephan J. Szyszkoski  
Surveyor's Michigan License No. 33986

Date 07/10/2012

For the Michigan Department of Natural Resources, Forest Resources Division

