

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 as Amended

For corners in

Marquette (County)	Located In:	Corner Code #
1. Public Land Survey	T 52N R 29W T 52N R 29W T R	G11 G8
2. Property Controlling in Section	S T R S T R S T R	
3. Miscellaneous Property in Sec.	S T R S T R	
4. Lot No. _____, Recorded Plat		
5. Private Claims		

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Stephan J. Szyszkoski, in a field survey on G11 05/17/2012 do hereby state
that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2
above were in conformance with regulations and rules therefore as required in the current manual of survey
instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of
a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with
the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established,
re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(G11) Corner common to Sections 27-28-33-34. 1846 - Established by Deputy Surveyors Hubbard and
Ives. Set post. Sugar 14" S15W 08 links, Fir 12" N58E 28 links. 1947 - Notes of Norman T. Thompson
RLS state "B.T.s gone. [Set] Hemlock post acc. to cross line old sq. tree. New B.T. Hemlock 4" N20E
8.2', Spr 9" S87W 10.5'." Found no subsequent record.

(G8) Quarter corner common to Sections 21 and 22. 1846 - Established by Deputy Surveyors Hubbard and
Ives. Set post. Hemlock 14" S47W 07 links, Hemlock 6" N56E 26 links. Found no subsequent record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

(G11) The original post and accessories were not recovered. Found a 1" ID I.pipe at record bearing
and distance from the 1947 NBTs. The NBT Hemlock N20E is now 20" DBH, in good condition, with upper
face and scribing visible. The Spruce S87W is a rotting stump at record bearing and distance. Found
other blazed trees adjacent as well as a metal location poster with many signatures. Accepted the
pipe as a careful and faithful perpetuation of the position of the original corner.

(G8) The original post and accessories were not recovered. Found no acceptable evidence of the
position of the original corner on the ground. Reestablished the position for the corner midway and
on the Section line between Section corners 2610.51' north and south, being proportionate to the
original record.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

(G11) Found 1"ID I.pipe and set plastic MDNR
cap PS 33986 inside.
Set measuring nail with MDNR tag in the side of:
4" Hemlock S57E 5.1' mrkd "S34 NBT"
11" Hemlock S56W 18.7' "S33 NBT"
7" Sugar N52W 18.8' "S28 NBT"
20" Hemlock N22E 7.7' old blaze (1947 NBT)
Set sq'd Cedar post adjacent.
Bearings are magnetic.

(G8) Set 1"IDx32" I.pipe with 4" alum. MDNR cap.
Set measuring nail with MDNR tag in the side of:
3" Y.Birch North 15.2' mrkd "1/4S NBT"
7" Maple N85E 12.0' do
5" Maple S63E 2.95' do
9" Maple S58W 4.5' do
Set sq'd cedar post adjacent.
Bearings are magnetic.

Signed by Stephan J. Szyszkoski
Surveyor's Michigan License No. 33986

Date 07/10/2012

For the Michigan Department of Natural Resources, Forest Resources Division

