LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MISSAUKEE
(County)

	Located In:	Corner Code ##
1. Public Land Survey	T 21N R 6W	K-8, K-9
	T ____ R ____	L-9
	T ____ R ____	
	T ____ R ____	
2. Property Controlling	S 23 T ____ R ____	7
in Section	S ____ T ____ R ____	
3. Miscellaneous	S ____ T ____ R ____	
Property in Sec.	S ____ T ____ R ____	

Register of Deeds Stamp & File Number

4. Lot No. _____ , Recorded Plat _____
5. Private Claims _____



I, CARL F. ROSER, in a field survey on JUNE 20, 19 91, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

K-8 K-9 L-9 7

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-8
REESTAB'D E 1/4 COR SEC 23 MIDWAY & ON LINE BETW SEC COR'S 1/2 MILE TO N & S. CTR WINDING N-S SAND TRAIL IS 80' WEST.

K-9
REESTAB'D NE COR SEC 26 MIDWAY & ON LINE BETW SEC COR'S 1 MILE N & 1 MILE S. S EDGE SMALL WET HOLE IS 110' ± N. REESTAB'D THIS COR BY SINGLE PROP MEA (S.P.) TO US (GLO) BECAUSE THIS TWP (T21N-R6W) SUB'N IS A GEN LAND OFFICE RESURVEY, 1852. THEY RAN RANDOM SO. 3 MILES FROM NE COR OF SEC 23 & CORRECTED BACK NORTH (STRAIGHT LINE) 3 MILES.

L-9
REESTAB'D N 1/4 COR SEC 25 MIDWAY & ON LINE BETWEEN NE & NW COR'S OF SEC 25. COR FALLS IN LARGE SWP. 1 1/2'± OF WATER.

7
ESTAB'D NE COR OF SE 1/4 OF NE 1/4 OF SEC 23 PER STANDARD BLM INSTRUCTIONS. CTR E-W WOODS TRAIL IS 98'± SOUTH.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-8
SET DNR MON & CED POST W/LOC TAG.

14" J PINE	N20°E	7.8'
16" J PINE	S46°E	52.5'
10" OAK	S08°W	34.1'
13" OAK	N62°W	27.8'

K-9
SET DNR MON & CED POST.

9" J PINE	N36°E	30.9'
7" R PINE	S38°E	38.1'
14" R PINE	S46°W	9.5'
6" W PINE	N82°W	58.4'
1 1/4" PIPE	N26°12'W	68.20'

L-9
DROVE 1" X 96" GALV PIPE W/ALUM DNR CAP. SET CED POST.

E'LY EDGE OF SWP	EAST	560'±
W'LY EDGE OF SWP	WEST	1060'±

NO OTHER WITS AVAILABLE.

7
DROVE 5/8" X 34" REROD W/LS CAP & SET CED POST W/LOC TAG.

14" J PINE	N78°W	23.8'
13" TW OAK	N40°W	10.1'
8" CHERRY	N14°E	44.6'
13" OAK	S16°W	6.9'

Signed by Carl F. Roser 12028 12-02-92 Date _____

Surveyor's Michigan License No. _____

STATE OF MICHIGAN
CARL F. ROSER
LAND SURVEYOR
No. 12028
REGISTERED LAND SURVEYOR

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983