

JAN 19 2000

LIBER 333 PAGE 452

SECTION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Missaukee County</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>8W</u>	<u>J-11</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

#1365

MISSAUKEE COUNTY MICHIGAN

RECORDED DEC 09 1999 4:10 PM

Carolyn Flare
Register of Deeds Stamp #654
Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Daniel E. Schripsema, in a field survey on October 1, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11												
12		31		32		33		34		35		36
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-11 - GLO - Set Post
16" Sugar N.1 1/2 E.6
8" Beech S.27 1/4 W.17

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" Iron North of centerline of E-W road. This corner was not accepted. Set 1/2" rered by single proration on line between I-11 and K-11. This corner is accepted as the best available evidence of the position of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1/2" rered and Missaukee County Monument


WITNESSES

S59W 167.97' Power Pole @ National Geodetic Witness Post
N78W 236.20 set nail in 24" Apple Tree
S71E 51.67' Set Iron
N03W 86.88' set nail in 16" Maple @ Fence line to North
East 3.62' found 1/2" iron

Peer Group Reviewed and Approved

Date: 12-2-99

J. Dean Coers
J. Dean Coers, Missaukee Co. Representative



Signed by Daniel E. Schripsema
Surveyor's Michigan License No. 24617

Date 12-2-99