

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
MISSAUKEE

Located In:

Corner Code: **44**

1. Public Land Survey

T 23N R 05W

G-4, G-5, H-5

T R

T R

T R

2. Property Controlling
in Section

S 10 T 23N R 05W

12

S T R

3. Miscellaneous
Property in Sec.

S T R

Register of Deeds Stamp & File Number

4. Lot No. Recorded Plat

5. Private Claims

I, **CARL F. ROSER**, in a field survey on **APRIL 15**, 19 **86**

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

C. (CONTINUED)

XXXXXXXXXXXXXXXXXXXX Description of original monument and accessories and/or subsequent restoration:

12

DROVE 5/8" X 34" REROD W/RLS CAP

& SET CED POST W/LOC TAG.

9" MAPLE N45°E 4.4'

8" TW MAPL N55°W 12.8'

8" MAPLE S15°W 9.4'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-4 PREVIOUS DEPT COR OF RECORD (K.J.O.-1967). KJO FD OLD POST BOTTOM THAT FIT ONE E.A. BEUTHIEN N.B.T. FROM HIS SUR & SEC SUB'N OF S-10, SEPT. 1914.

G-5 PREV DEPT COR OF RECORD (K.J.O.-1967). FITS E.A. BEUTHIEN SUR & SEC SUB'N OF S-10; SEPT 1914. K.J.O. FD VERY OLD SCRIBED SQ POST AT FN CORNER.

H-5 PREV DEPT COR OF RECORD (K.J.O.-1967). KJO'S FIELD NOTES (PROBABLY KEITH SACKETT) INDICATE THEY FD SQ POST HERE. COR FALLS IN 5" OF WATER NEAR SW'LY EDGE OF TAG ALDER SWP. EDGE OF ALDER & START OF LITTLE HIGHER GRD IS 20'± SOUTH.

12 ESTAB. NW COR OF SW 1/4 - SE 1/4 PER STANDARD BLM INSTRUCTIONS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-4

G-5

H-5

FD DEPT MON, CED POST
& STEEL FN POST.

FD DEPT MON, SQ CED POST,
& STEEL FN POST.

FD DEPT MON, ADDED CED POST

5" MAPLE CLMP N84°E 21.1'

9" ELM STB N34°W 18.7'

6" W BIRCH S20°E 47.6'

8" TW MAPL N34°E 23.3'

18" MAPL CLMP N56°E 18.6'

5" MAPLE S05°W 14.4'

3" W PINE N40°W 25.7'

8" ELM N80°E 5.8'

6" W BIRCH S60°W 18.7'

*30" W PINE S78°W 81.1'

18" ELM STB. SOUTH 30.77'


* (KJO 1967 Writ)

Signed by Carl F. Roser 05-06-86

Date

Surveyor's Michigan License No.

12028



FORM APPROVED BY MICHIGAN BOARD OF LAND SURVEYORS, JAN. 25, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983