

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 24 N.R. 7 W


Missaukee COUNTY

DESCRIPTION OF CORNER 1/4 corner common to Sections 7-8

CORNER MONUMENT Set 1" pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED June 14, 1966

WITNESSES TO CORNER.....



7" R. Oak S 29 W 8.9'

10" R. Oak N 8 E 7.7'

AND Concrete pipe Mon. N 25 E 48.7'

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was found while making a retracement in this township. Set corner from SE USBT stump which is in place with good benchmark. One of few original corners found in township, and cannot explain how it was missed in early county surveyor retracement of this township. Left pipe - concrete monument in place- but obviously erroneously established.

SURVEYOR'S SEAL

SIGNED *Lucretia J. Ostling* DATE June 14, 1966
REGISTERED LAND SURVEYOR #10068