

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 31 N. R. 2 E.	B-7; C-5; C-6; C-7
2. PROPERTY CONTROLLING IN SECTION	T. N. S. R. E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. S. R. E. W.	
4. LOT NO. , RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on July 28, 1977, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 7 Found 1½" pipe at corner as perpetuated by local residents in mid-1930's. One possible USBT stump in place.
- 5 Set corner on line, at proportionate measurement, between ¼ corners north and south which conforms very well with US line tree stp. location 234' N. Could not positively identify US evidence.
- 6 Fd. 1½" pipe (set by local resident) in position probably as reestablished by F. Smith in 1932. Smith NBT stumps in place & stumps in place for USBT's.
- 7 Set corner at intersection of line over ¼ and section corner N and ¼ and section corner W. This point faced by very old scribed witness stub SE but could not find previous corner

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: in swamp.

B-7

C-5

C-6

Set DNR mon. & cedar post	Set DNR mon. & cedar post	Set DNR mon. & cedar post
22" R. Pine N85°E 93.3	11" R. Pine S16°E 38.2	12" R. Pine N85°W 23.6
17" R. Pine N07°E 39.8	12" W. Oak N32°E 76.1	3" R. Pine S18°E 50.1

C-7

Set DNR mon. & cedar post
20" Tam.stp. (old witness) S43°E 17.2
5" Cedar S55°W 32.6
7" Cedar S55°W 36.9

SIGNED BY Kenneth J. Ostling

DATE 1

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:


SIGNED BY _____

DATE _____

APPROVED AND SIGNED BY _____

MICHIGAN REGISTERED LAND SURVEYOR

DATE _____



(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

MONTMORENCY COUNTY