

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECEIVED  
MONTMORENCY CITY  
REGISTERED DEEDS  
DEC 20 10 12 AM '93  
A. PANGAR-MCELROY

For corners in

Montmorency  
(County)

Located In:

Corner Code #

1. Public Land Survey T 32N R 1E A-11  
T 32N R 1E A-12 ✓  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

APPROVED BY  
PEER GROUP

NOV 05 93

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

Donald E. Marlatt, in a field survey on December 10, 19 93,  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

6. Description of original monument and accessories and/or subsequent restoration:

- |   |   |
|---|---|
| <p>A-11) S.W. Cor. Sec. 30, T32N, R1E<br/>Post Cor. set by Austin Burt 1850.<br/>Tamarack 8-S 33 W-15<br/>Tamarack 8-N 55 E-25<br/>Survey by Duane MacNeill for<br/>Steve Fletcher Nov. 1988.</p> | <p>(A-12) W. ¼ Cor. Sec. 31; T32N, R1E<br/>Post Cor. set by Austin Burt 1850.<br/>Pine 16-N 2 W-54<br/>Pine 6-S 1 W-20<br/>Survey by Duane MacNeill for<br/>Steve Fletcher Nov. 1988.</p> |
|---|---|

7. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- |  |  |
|--|--|
| <p>A-11) S.W. Cor. Sec. 30, T32N, R1E<br/>Fnd. ½" rod &amp; 1" pipe with cap #19237<br/>S 74° E 10" Cedar 34.71'<br/>S 75° W 17" N. Pine 57.5'</p> | <p>(A-12) W. ¼ Cor. Sec. 31, T32N, R1E<br/>Fnd. 1" pipe &amp; cap #19237</p> |
|--|--|

No evidence of original corner.

No evidence of original corner.

The Peer Group approved (A-11) & (A-12) as the best available evidence of the  
reestablishment of the original corner.

8. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |   |   |
|---|---|
| <p>A-11) S.W. Cor. Sec. 30, T32N, R1E<br/>Placed Co. Re-Mon. cap on ½" rod.<br/>S 74° E 10" Cedar 34.71'<br/>N 12° E 9" Spruce 27.54'<br/>N 89° W 11" Spruce 36.95'<br/>S 75° W 17" N. Pine 57.5'</p> | <p>(A-12) W. ¼ Cor. Sec. 31, T32N, R1E<br/>Placed Co. Re-Mon. cap on 1" pipe.<br/>S 7° E 10" N. Pine 21.07'<br/>S 54° W 10" N. Pine 14.58'<br/>N 50° E 15" Oak 45.30'<br/>S 75° E 9" Maple 42.95'</p> |
|---|---|

Note: Witnesses marked with 30 penny spikes & I.D. tags #18660.

Signed by Donald E. Marlatt

Date Dec 15, 1993

Surveyor's Michigan License No. 18660

