

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 32 N.R. 4 E


Montmorency COUNTY

DESCRIPTION OF CORNER 1/4 Corner common to Sections 30-31

CORNER MONUMENT Set 1" pipe with 1/4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED May 24, 1966

WITNESSES TO CORNER.....



20" B. Oak N10W 42.5'

18" B. Oak S76E 50.0'

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set while making a survey of Section 30. Set section corners at U.S. record distance from section corner west on town line. This point checks most of the calls of the U. S. Record for the W 1/2 mile and leaves the apparent shortage in the E 1/2 mile where it probably occurred. Unable to proportion entire shortage over mile and fit the calls of the U. S. notes. No definite evidence of U.S. stumps.

SURVEYOR'S SEAL

SIGNED Kenneth J. Ostling DATE June 7, 1966  
REGISTERED LAND SURVEYOR #10068