

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

Ontonagon County

Page 1 of 1

LC 5/290

JEN Date 06/12/2000

Time 16:31:34

RECORDING FEE:

9.00

For corners in

Ontonagon County

Located in:

Corner Code #

1. Public Land Survey T52N R39W L - 5

T R

T R

T R

2. Property Controlling in Section S T R

S

T R

S

T R

3. Miscellaneous Property in Sec. S T R

S

T R

4. Lot No.

Recorded Plat

5. Private Claims

SURVEY & REMONUMENTATION

MAR 02 2001

SECTION

Register of Deeds Stamp & File Number

I, Joseph C. Domitrovich, in a field survey on May 22, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

(L - 5) ¼ Corner Common to Sections 12 & 13, T52N, R39W.

1845 - William A. Burt set a Sugar Post with ties:

16" Hemlock	N 17°E	37 links
14" Cedar	N 61°W	21 links

I found no record of subsequent restoration.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I found no remains of the original corner or accessories. A paved North - South county road now runs along the N - S ¼ line, and an old fence line runs along the North line of Section 13. I created a position for the ¼ corner at the intersection of centerline of the county road and extension of fence lines East and West. This position works well with section corner to East and West as well as with long time occupation. I accepted the fence and centerline intersection as the ¼ corner.

Research on file with County Remonumentation Representative.

DEED GROUP APPROVED



COUNTY SUPERVISOR

5-24-00

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:


Corner is a 5/8" x 12" iron pin with a 3" diameter aluminum cap stamped to read: COUNTY REMONUMENTATION; T52N, R39W; ¼ S. 12, S. 13; 2000; P.S. 37273. I also established a Reference Monument (R.M.) to the east, a ½" x 48" aluminum rod with a 3" diameter cap stamped to indicate that the ¼ corner is S 89°54'W, 28.16'. Ties to the corner:

Power Pole	S 59°E	33.01'
8" Red Pine	N 84°W	35.57'
12" White Pine	N 49°E	41.01'
R.M.	N 89°54'10"E	28.16'
NE Cor. Sec. 13	N 89°44'18"E	2628.04'
NW Cor. Sec. 13	S 89°28'44"W	2654.19'



NOTE: Bearings to witness objects are magnetic. Distances are to a nail in side of the witness object unless noted.

Signed by



Date

5/24/00

Surveyor's Michigan License No. 37273