

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 19 N. R. 9 E.	E-13 G-13
2. PROPERTY CONTROLLING IN SECTION 34	T. 19 N. R. 9 E.	Code 3
3. MISCELLANEOUS PROPERTY IN SECTION	T. N. R. E.	
4. LOT NO. , RECORDED PLAT		
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Kenneth J. Ostling do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on 11-9 1972, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

E-13: Temple 1892 found USBT. Set Mon and marked: Pine stp 30 S11E 54
Pine stp 26 S50W 80

G-13: A. Temple 1892. Found stump of closing corner witness and set corner accordingly. Set monument and marked: Pine stp 20 S49W 21
Pine stp 14 S63E 26

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-13 Found Temple tile monument and witness stumps.

G-13 Found Temple monument and his witness stumps.

Cd. 3 Set corner by standard survey procedure for the subdivision of sections.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-13
Left 1 1/2" pipe & tile mon
in place.
24" Oak S85E 63.0
10" Maple S33E 56.6
27" Maple Due S 55.1

G-13
Left 1/2" bar in 3" tile
in place. Added Ced. Guard
Post & tag.
9" S. Maple (5 cl) N62E 38.2'
30" P.Stp N75E 34'
18" R. Oak N85W 52.0'
(clp of two)

Code 3
Set 1"x36" pipe & Cedar
Post
(18" R. Oak) N20E 28.0
(clp of two)
14" R.Oak) Due W 25.2
clp of two)
10" Maple) N30W 40.3
Clmp of 3)


SIGNED BY Kenneth J. Ostling DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. 10068

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. _____