

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON

(County)

Located In:

Corner Code #

1. Public Land Survey

T48NR 39W

B-11

T R

T R

T R

T R

2. Property Controlling
in Section

S

T R

S

T R

3. Miscellaneous
Property in Sec.

S

T R

S

T R

SURVEY &
REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat

5. Private Claims

$\frac{1}{4}$ Corner common to Sections 30 & 31, T48N 39W.

I, Earl W. Applekamp, in a field survey on July 29, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Artemas Curtis, U.S. Deputy Surveyor, September 16, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

Hemlock 18" N82°E 10.56 feet
Sugar 15" S58°W 14.52 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. At the apparent corner position there was a well maintained fence running North & South separating two property owners. An old fence which was down ran East from the position. Corner was re-established at this position. This position is in conformance with the distances on the GLO notes.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED

Earl W. Applekamp
COUNTY REPRESENTATIVE

8-14-96

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 2 $\frac{1}{2}$ "x30" aluminum pipe with a 3 $\frac{1}{4}$ " cap stamped to read: County Remonumentation, T48N R39W, $\frac{1}{4}$, S30, S31, 1996, P.S. 17610. I established four bearing trees & objects.

11" Aspen N40°W 62.15' 6" Aspen N32°E 26.80'
4" Aspen S43°E 42.08' Steel Sign Post East 1.30'



Signed by Earl W. Applekamp

Date August 13, 1996

Surveyor's Michigan License No. 17610