

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

ONTONAGON (County)	Located In:	Corner Code #
1. Public Land Survey	T48N R 41W	G-6
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property In Sec.	S T R	
	S T R	

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

$\frac{1}{4}$ Corner common to Sections 15 & 16, T48N R41W.

I, Earl W. Applekamp, in a field survey on Nov. 29, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by Wells Burt, U.S. Deputy Surveyor, June 15, 1851. Set Wood Post.

ORIGINAL BEARING TREES:

10" Spruce	N65°	22.44 feet
12" Spruce	S22°W	13.20 feet

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No original evidence was found. Corner was re-established by single proportionate measure. Corner position falls in a small creek and swamp condition. An existing fence, in poor condition is 30 feet East of the corner position.

Research on file with the Ontonagon County Remonumentation Program Representative.

PEER GROUP APPROVED
Earl W. Applekamp
COUNTY REPRESENTATIVE
12-02-97

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a $\frac{3}{4}$ "x5 $\frac{1}{2}$ " aluminum rod with a 3" cap stamped to read: County Remonumentation, T48N R41W, $\frac{1}{4}$, S15, S16, 1997. P.S. 17610. I established three bearing trees and a reference object.

7" Aspen	S08°E	83.20 feet	-	18" Spruce	N35°W	127.30 feet
3" Balsam	S10°W	58.98 feet	-	6' Steel Sign Post,	West	0.63 feet



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date November 29, 1997