

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
ONTONAGON
(County)

Located In:

Corner Code #

1. Public Land Survey T 51N R 41W 002
T R
T R
T R
2. Property Controlling S T R
In Section S T R
3. Miscellaneous S T R
Property in Section S T R

SURVEY &
REMONUMENTATION

MAY 22 1997

COMMISSION

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

Meander Corner between Section 7 & 8, T51N R41W.

I, Earl W. Applekamp, in a field survey on December 04, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Original corner established by S.W. Higgins, U.S. Deputy Surveyor in 1847. Set wood post.

ORIGINAL BEARING TREES:

Cedar 12" S05°W 149 links - Cedar 8" S20°E 202 links

In November, 1966, Billy D. Buckler, RLS, No. 8887, set a 1½" Iron Pipe with a 4" aluminum cap. On December 10, 1981, William Immich, RLS, No. 27448, performed a survey in this area and used this corner. He recorded the corner under Act 74 in Liber, 2, page 7.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

I recovered the corner 2 feet below the sand, I could not raise the monument, so I left it in place and set a new monument described below.

Research on file with the Ontonagon County Remonumentation Program Representative.


PEER GROUP APPROVED

Earl W. Applekamp 12-11-96
COUNTY REPRESENTATIVE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

At the corner position I set a 7/8"x12 feet aluminum rod with a 3½" cap stamped to read: County Remonumentation, T51N R41W, M.C., S7, S8, 1996, P.S. 17610. This monument projects 2 feet above the sand. I established the following bearing trees and reference objects. Centerline of Michigan Hwy. M-64 is 82.9 feet South.

8" Ash S46°W 58.45 feet - 10" Ash S40°E 49.30 feet
11" Ash S61°E 57.25 feet - Steel sign post North 0.72 feet



Signed by Earl W. Applekamp
Surveyor's Michigan License No. 17610

Date December 09, 1996