

**LAND CORNER RECORDATION CERTIFICATE**  
**FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970**

FOR CORNERS OF—	LOCATED IN—	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY	T. 35 N. R. 4 E.	A-13; B-13; C-13
2. PROPERTY CONTROLLING IN SECTION	31 T. 35 N. R. 4 E.	15
3. MISCELLANEOUS PROPERTY IN SECTION	T. S. R. W.	
4. LOT NO.	RECORDED PLAT	
5. PRIVATE CLAIMS		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Kenneth J. Ostling, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on April 30, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-13 Found monument in place as restored by Presque Isle County Surveyor.
- B-13 Set by proportionate measurement between section corners. No evidence of a previous corner.
- C-13 Set by single proportionate measurement between corners ½ mile east and 1 mile west.
- 15 Set by standard survey procedure for the subdivision of sections.


C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A-13	B-13	C-13
Fd Presque Isle Co. Mon. in place	Set DNR Monument	Set DNR Monument
7" R. Pine N54°W 42.9'	6" R. Pine S03°W 77.3'	9" R. Pine S63°W 5.0'
12" Tw. Oak N33°E 38.8'	8" J. Pine S52°W 45.9'	9" R. Pine N19°E 5.3'
Cedarpost NE 30'		

10  
Set 5/8" Rod w/RLS Cap  
4" Oak S41°E 26.0'  
5" Oak S23°W 14.5'

SIGNED BY Kenneth J. Ostling  
SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_  
FOR STATE AND UNITED STATES AGENCIES:

DATE 9/4/80



SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
APPROVED AND SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_