11BER 339 PAGE 820

PRESQUE ISLE COUNTY RECORDED

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN

2000 OCT 30 PM 3: 28 not M. Samp REGISTER OF DEEDS SURVEY & REMONUMENTATION FEB 1 2 2001 Register och File Number

For corners in	2000	PRESQUE	ISLE (COUNTY, MENTATI	STATE	OF	MICHIGA
Presque Isle		Locate			ner Code #		
(Co	ounty)						
1. Public Lan	d Survey	1	T <u>35N</u> F T <u>35N</u> F T F	2E	G-12 H-11	_	
Property Control in Section Miscellane Property in	ous	g S S S S	TF TF TF				
4. Lot No	, F	lecorded Plat	·				

I, <u>Delmer E. Porter</u>, in a field survey on <u>09/5/00</u>, 19 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in 09/5/00_, 19 conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below: NOTE: Not more than 2 corners, all in the same town and range, may be recorded

on this certificate.


1	A E	3 (; <u> </u>) <u>I</u>	5 I	7 (; ;	_	Ī,	<i>J</i> 1	ζ <u>I</u>	, N
2		[6—	_		<u> </u>	ļ —	<u> </u>] 3	<u> </u> -:	! ?	-	ļ_
3			_				ļ <u>.</u>	<u> </u>	ļ			
4	·] 	-	3	-	 9	_1	<u> </u> -	1	1	11	2—
5					<u> </u>			-		\vdash	┼	
6	1	8	1	7—	<u> </u>	6	1	5	<u> </u> -1	4	 1	3
7								ļ		<u> </u>		<u> </u>
8	1	9	2	0	2	1	2	2	2	1 3—	2	ļ 4
9								L		L		
10	2	0		9		8		7	L_2	6—	2	 5
		ľ	-			ĺ				ľ		Ī
11												
12	3	1	3	2	 3	3) 3	4	-3	5 I	3	6— 1
13	L	<u> </u>	<u> </u>			L	L			<u>L</u>		

A. Description of original monument and accessories and/or subsequent restoration:

G-12 1/2" ROD BY CEDAR STAKE S 20° W 82.38' 15" ASH S 77° W 9.65' 4" ASPEN N 17° E 6.68' 5" ASPEN S 66° E 9.00' 8" ASPEN

5. Private Claims

1" PIPE N 71° E 53.13' 12" MAPLE S 35° E 102.37' P. POLE SOUTH 3.0' RD C/L



Ratified by Peer Group in accordance with P.A. 345 1 Qua

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

G-12 1/2" ROD S 20° W 82.38' 15" ASH S 77° W 9.65' 6" ASPEN N 17° E 6.68' 7" ASPEN S 66° E 9.00' 9" ASPEN

1" PIPE S 54° W 38.38' 10" BOX ELDER N 15° W 44.37' 14" MAPLE N 73° E 43.40' 19" BAM S 33° W 28 30' 7" APPLE

"WITNESS TAGS & NAILS USED.

Signed by Delmer & Anto	Date	
Surveyor's Michigan License No. 15410		