

SURVEY & REMONUMENTATION

APR 07 1998

SECTION

9206

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For Corners in <u>Roscommon</u> (County)	Located in:	Corner Code #
1. Public Land Survey	T <u>21N</u> R <u>1W</u>	<u>F-5</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

STATE OF MICHIGAN
ROSCOMMON COUNTY
RECORDED

16 DEC 97 10:15 A.M.

ROBERT W. SMITH
REGISTER OF DEEDS

FILE IN LIBER 3 OF LAND CORNERS
Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, Gerald J. Gray, in a field survey on May 11, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4, and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Note: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1) Wm. A. Burt 1850
Cedar 6 S80W 14
Tam. 12 N40E 13
- 2) G.F. Delamater 6/19/1935, L. 1, P. 77
Found both Gov. B's, No post
Set 1/2" iron rod
Cedar 6, N9E 23.0'
Cedar 8, S81E 27.9'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

ROSCOMMON COUNTY
PEER GROUP APPROVAL

DATE MAY 17, 1994

Marvin E. Myers
Marvin E. Myers, P.S.
County Surveyor

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:


Found 1/2" iron rod at south edge of water in creek. Cedar trees in the area are all dead and windfallen.
Also found 3/4" pipe S55°E 30.20'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Standard Roscommon County Monument

Set Nail	4" Maple	S55°E 45.88'
Set Nail	8" W. Oak	S25°E 43.87'
Set Nail	6" Maple	S03°E 35.84'
Set Nail	Twin 6" Maple	N22°W 63.67'

Signed by Gerald J. Gray Date
Surveyor's Michigan License No. 17741



FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 25, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983

LIBER 3 PAGE 440